

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/21/06

CORNER DESIGNATION: 2N31, G-5, The East One-Quarter Corner of Section 7.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner, drove charred stake and raised mound with trench, as per instructions. John Kimbrell, in survey recorded at Book 1, Page 348, surveyed through this corner but did not recover or reestablish it.

MONUMENT AND ACCESSORIES FOUND:
Found and held a point at fence projections with fences North and West as best remaining evidence of original corner. Corner point is South 25° East - 4.0' from a railroad tie fence corner and gate post. There is evidence (by wood post remains) that the fence continued East at one time.

MONUMENT MARKING DETAIL:
T2N R31E
1
4
S7|S8
2006
PLS 1106

MONUMENT SET:
At accepted corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with top 8" above ground level and raised a mound of earth and stone to top of cap, monument marked as shown.

From which:
A 5/8" x 24" rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 11° East, 32.4 feet.
A 5/8" x 24" rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 74 1/2° East, 34.3 feet.
A 5/8" x 24" rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 09 1/2° East, 37.2 feet.
A 5/8" x 24" rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 64 1/2° West, 19.5 feet.
Attached bearing object signs to all rebar accessories. Nailed witness sign to railroad tie fence post North 25° West, 4 feet from monument.

LOCATION AND COMMENTS: Corner located on Southeast facing slope at edge of farmed field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:
N = 733162.79
E = 8592192.85


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31G5



renews 6-30-08

11-11-20