

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 03/2/06

CORNER DESIGNATION: 2N31, J-1, The Southwest One-Quarter Corner of Section 7.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David P. Thompson, under Contract No. 81, dated July 8, 1959. Record states: Set post for corner to Secs. 12, 13, 7 & 18 and build mound of earth with pits, trench &c., as per instructions. Corner shows on relocated Right-of-Way and Track Maps for O.W.R.R. and N. Co., as being 1864 feet South of relocated track centerline. J.C. Arnold, in 1888 survey recorded in Book 1, Page 203, recovers the charred end of the original post and remonuments the corner with a 13 x 10 x 5 inch stone. John Kimbrell, in 1904 survey recorded at Book 1, Page 550, (and also Book 1, Page 556, with same date) reestablishes the corner and monuments with a 18 x 8 x 6 inch stone.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N  
R30E|R31E  
S12|S7  
S13| S18  
2006  
PLS 1106

MONUMENT SET:

Re-established corner on line between the recovered Northwest corner of Section 7 and the West One-Quarter corner of Section 18, at a distance of 1864.00 feet Southerly from the Railroad Main Line Track centerline. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" by 30" galvanized iron pipe with cap 16" below ground level.

From which:

- A Silver Deep-1 magnet buried 24" in the ground bears North 52° East, 27.6 feet.
  - A Blue Deep-1 magnet buried 24" in the ground bears South 30° East, 31.3 feet.
  - A Purple Deep-1 magnet buried 24" in the ground bears South 54° West, 29.1 feet.
  - An Orange Deep-1 magnet buried 24" in the ground bears North 41° West, 29.1 feet.
- Buried bearing object signs with all magnets. Attached bearing object sign and witness sign to a wood fence corner post 1290' +/- North of monument.

LOCATION AND COMMENTS: Corner is located in a once farmed field, now in CRP, approximately 1290' South of a wood fence corner post with witness sign and bearing object sign attached.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 730762.89  
E = 8586554.59



FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31J1



renews 6-30-08

06-462-c