

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/15/06

CORNER DESIGNATION: 2N31, J-3, The South One-Quarter Corner of Section 7.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner, drove charred stake and raised mound with trench, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N R31E
1 S7
4 S18
2006
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure between the reestablished Northeast and Northwest corners of Section 18. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 16" below ground level in a farmed field. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 24" below ground bears North 77° East, 30.2 feet.
 - A blue Deep-1 magnet buried 24" below ground bears South 06° East, 34.6 feet.
 - A purple Deep-1 magnet buried 24" below ground bears South 76° West, 38.8 feet.
 - An orange Deep-1 magnet buried 24" below ground bears North 21° West, 33.8 feet.
- Buried bearing object signs with magnets. Nailed witness sign on railroad tie h-brace in railroad right-of-way fence North 04 1/2° West, 275' +/- from monument.

LOCATION AND COMMENTS: Corner is buried in a farmed field approximately 275 feet South of South railroad right-of-way fence.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 730641.92
E = 8589666.03

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31J3

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

06-462-C