

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/7/06

CORNER DESIGNATION: 2N31, J-7, The South One-Quarter Corner of Section 8.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner, drove charred stake and raised mound with trench, as per instructions. John Kimbrell indicates he reestablished this corner in survey recorded in Book 1, Page 348. Record states: "From the 1/4 Sec Corner bet Secs 8 & 17 previously set on Railroad Embankment 20 feet from Track....". Note: The railroad track referred to has been relocated. Corner surveyed through and not recovered on 1971 Survey No. 03-293-B, PLS 933.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N R31E
1/4 S8
4 S17
2006
PLS 1106

MONUMENT SET:

Re-established corner position by single proportionate measure between the reestablished Northwest and Northeast corners of section 17. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe, 28" in the ground. Monument marked as shown in monument marking detail.

From which:

A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" at the base of a gate post bears North 09° East, 76.9 feet.

A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" in fence line bears South 04° East, 16.8 feet.

A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 72 1/2° East, 79.8 feet.

A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" in fence line bears North 26 1/2° West, 27.9 feet.

Attached bearing object signs to rebar accessories. Nailed witness sign to wood fence post 4' West of corner.

LOCATION AND COMMENTS: Corner is located 4 feet East of Easterly right-of-way fence along highway and 25 feet East of centerline of highway pavement. A house on West side of road bears North 35° West, 300 feet +/-.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 730611.61
E = 8594923.79

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31J7



William R. Wells



renews 6-30-08

06-462-C