

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 01/31/06

CORNER DESIGNATION: 2N31, L5, The East One-Quarter Corner of Section 18.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner, drove charred stake and raised mound with trench, as per instructions.

John Kimbrell, in survey recorded at Book 1, Page 348, recovers this corner and states: "intersect 1/4 Sec corner bet 17 & 18".

This corner was surveyed through on Survey No. 03-293-B, (not recovered).

**MONUMENT AND ACCESSORIES FOUND:**

Found and held the center of a 3 1/2 foot diameter, old flat mound of stone on rocky ridge top as best remaining evidence of the original corner. Mound of stone is located approximately 15' West of an old fence running North and South down the ridge top. Found evidence of old wood posts and old fence wire 350' North. There are a few wood posts scattered in the corner area.

**MONUMENT MARKING DETAIL:**

T2N R31E  
1/4  
S18|S17  
2006  
PLS 1106

**MONUMENT SET:**

At the center of the mound of stone set a 5/8" x 24" rebar with 2" aluminum cap 8" in the ground to bedrock and surrounded it with a mound of stone and earth. Monument marked as shown in monument marking detail.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 57 1/2° East, 93.9 feet.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 71° East, 94.1 feet.

"XBO" in the top of a 24"x18"x6" (exposed area) immovable rock outcrop bears, South 71 1/2° West, 36.8 feet.

"XBO" in the top of a 36"x18"x8" (exposed area) immovable rock outcrop bears, North 47° West, 37.0 feet.

Attached bearing object signs to all rebar accessories. Wired witness sign to 26"x9"x8" stone and placed stone at South edge of mound of stone.

**LOCATION AND COMMENTS:**

Corner is located just West of the top of a rocky ridge running North-South. There are two human built rock stacks, visible from many locations, on a rock outcrop approximately 300' North of the corner.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 728040.13  
E = 8592373.03

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

/2N31L5

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

06-462-c