

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/30/06

CORNER DESIGNATION: 2N31, N-11, The South One-Quarter Corner of Section 16.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: "Set post for 1/4 Sec. corner and raised stone mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner falls on steep hillside.

MONUMENT MARKING DETAIL:

T2N R31E
1 S16
4 S21
2006
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure between the recovered Southwest and Southeast corners of Section 16. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" by 30" galvanized iron pipe, 29" in the ground and surround with mound of earth and stone. Monument marked as shown in Monument Marking Detail.

From which:

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 50° East, 44.5 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 31° East, 32.1 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 80 1/2° West, 28.9 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 36° West, 45.3 feet.

Attached bearing object signs to all iron rebar accessories. Set steel fence post with witness sign 2' East of monument.

LOCATION AND COMMENTS: Corner is located 30'+- West of a draw running Northwest, on steep hillside East of one of Steve Wolfes cattle feeding stations.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 725448.66
E = 8600203.57

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31N11

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-06