

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 03/7/06

CORNER DESIGNATION: 2N31, N-17, The Southwest One-Quarter Corner of Section 14.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for corner to Secs. 14, 15, 22 and 23, drove charred stake and raised mound with trench, as per instructions. John Kimbrell, in survey recorded at Book 1, Page 348, recovered the original corner. Record states "the corner to Secs 14-15-22-23 old Post in mound, Pits & etc.". The Kimbrell survey calls this corner 412.5' (6.25 chains), South of a "Rocky Cliff, 481 feet high by triangulation".

MONUMENT AND ACCESSORIES FOUND: None. Corner falls in a previously farmed field, now in CRP.

**MONUMENT MARKING DETAIL:**

T2N R31E  
S15|S14  
S22| S23  
2006  
PLS 1106

**MONUMENT SET:**

I located the top of the cliff north of the corner point, (referred to on the Kimbrell survey). I then calculated the record proportioned departure between the recovered South one-quarter corners of Section 14 and 15. I reestablished the corner position 412.5 feet South of the top of the cliff, at the record proportioned departure point. Reestablished corner position matches Kimbrells measured distance to the Northwest corner of Section 14, very well. At the reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 12" below ground level.

From which:

- A Silver Deep-1 magnet buried 20" in the ground bears North 49 1/2° East, 28.6 feet.
  - A Blue Deep-1 magnet buried 20" in the ground bears South 42° East, 37.6 feet.
  - A Purple Deep-1 magnet buried 20" in the ground bears South 42° West, 32.5 feet.
  - An Orange Deep-1 magnet buried 20" in the ground bears North 30° West, 26.0 feet.
- Buried bearing object signs with all magnets.

LOCATION AND COMMENTS: Corner is located in a once farmed field, now in CRP, approximately 300 feet South of a field fence South of the rock cliff. From the corner, the Pendleton weather station weather globe at the airport bears North 44° East. A metal fence angle brace post in the fence running along the bluff (only metal brace post visible from the corner) bears North 20 1/2° West, 350 feet +/-.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 725614.90  
E = 8608141.25

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31N17



*William R. Wells*



*renews 6-30-08*

*06-462-C*