

RTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. N-1

Note: Monument marked as shown below


History of original corner establishment:

This corner was originally established by Josiah A. Burnett, U.S. Deputy Surveyor, under Contract No. 92, dated September 12, 1860. The original notes state:

Set Post for corner to Secs. 13, 24, 18 & 19 from which:

A willow, 5 ins. diam. bears N 52 W, 51 links dist.

No other bearing trees convenient, drove charred stake and raised mound with trench, as per instructions.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

None, corner falls in the eroded channel of Birch Creek.

Reestablished corner by single proportion measure between the West 1/4 corner of Section 18 and the West 1/4 corner of Section 19.

Description of monument and accessories | established to perpetuate the original location of this corner:

At a point N 00° 03' 16" W, 40.0' from true corner point, on section line, set a 2 1/2" brass cap on a 1 1/4" x 30" galv. iron pipe with cap buried 18" below ground in edge of alfalfa field. Witness corner is about 20' East of East bank of Birch creek. From the witness corner monument:

A 5/8" x 30" iron pin bears S 58° W, 9.4' and is capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106".

A 5/8" X 30" iron pin bears N 40° 51' W, 220.4' and is capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106".

A brass washer stamped "PLS 1106" bears N 41° 35' W, 285.8'. Washer is nailed to N.E. side of PP&L pole 139002, 1' above ground.

A Bearing Object sign is attached to the pole.

The most N.E. corner of bridge wing wall bears N 36° 14' W, 432.5'. This bridge is on the County Road, where it crosses Birch Creek.

Set steel fence posts by each pin and attached Bearing Object signs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....

..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71)

Umatilla County Surveyor

★ GPO—798-276

Date 8-92

Rec'd By KE

No. 92-92-C