

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/2/06

CORNER DESIGNATION: 2N31, N-3, The South One-Quarter Corner of Section 18.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner, drove charred stake and raised mound with trench, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N R31E
1 S18
4 S19
2006
PLS 1106

MONUMENT SET:

Reestablished corner by single proportionate measure between the recovered Southwest and Southeast corners of Section 18. At the reestablished corner position, there are a few old wood posts which are burned indicating a fence at one time in the past. There is no indication at this time of the direction(s) the fence may have ran. Set a 5/8" x 24" iron rebar, 20" in the ground to bedrock with a 2" aluminum cap attached. Surrounded with mound of earth and stones. Set a steel fence post with witness sign 1 foot West of monument.

From which:

A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap stamped "OR PLS 1106 WA PLS 17372" bears North 33° East, 36.0 feet.

A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap stamped "OR PLS 1106 WA PLS 17372" bears South 44° East, 26.5 feet.

A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap stamped "OR PLS 1106 WA PLS 17372" bears South 42° West, 28.6 feet.

A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap stamped "OR PLS 1106 WA PLS 17372" bears North 59° West, 36.0 feet.

Attached bearing object signs to all rebar accessories.

LOCATION AND COMMENTS: Corner is located on a steep hillside sloping West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 725475.43

E = 8589761.24

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/2N31N3

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

06462-c