

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.


Corner Code No. A-13

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by D. Thompson, U.S. Deputy Surveyor, under Contract No. 106, dated August 16, 1864. The original notes state that at the corner a wood post, with charred stake, earth mound and pits was set for the corner.

The only other reference to the corner found in county records was when John Kimbrell recovered the corner and used it to reestablish the 1/4 corner common to Sections 4 and 3 in 1907.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

None. This corner was reestablished by single proportion measure between the reestablished N.E. corner of Section 3 and the N.E. corner of Section 5.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the reestablished corner position, I set a 2 1/2" brass cap on a 1 1/2" galv. iron pipe in the edge of a wheat field. The top of the monument is 14" below ground surface. The bottom of the monument is buried to bedrock. The monument is located about 2.5' north of the south edge of a wheat field. Set reference monuments as follows. From the reestablished corner position:

A 1 1/2" yellow plastic cap marked "W.R. Wells PLS 1106", set on a 5/8" by 30" iron rod bears S22°W 17.24'.

A 1 1/2" aluminum cap, marked as shown, set on a 5/8" by 30" iron rod bears S42°E 18.44'.

Set steel fence post with witness corner sign attached 3.4' south of the corner monument.


Set steel fence posts near each reference monument and attached witness corner and bearing object signs to each post.

The aluminum cap on the reference monument is marked:

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19....

..... by
(COUNTY OFFICIAL) (DEPUTY)