

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.


Corner Code No. A-7

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by D. Thompson, U.S. Deputy Surveyor, under Contract No. 106, dated August 16, 1864. The original notes state that at the corner a wood post, with charred stake, earth mound and pits was established for the corner.

This corner was reestablished by single proportion measure between the N.W. and N.E. corners of Section 5 by City crews in the 1950's. The existing corner monument was installed by the City at a later date, but the City's corner card does not note the date.



Corner No.  
Compass Declination: 18.0

Description of corner evidence found:

Found a 1 3/4" brass disc, set flush in concrete. The cap had on the marks "CITY OF PENDLETON" on it. Marks were added by this surveyor and the cap now appears as shown in the corner diagram.

Description of monument and accessories I established to perpetuate the original location of this corner:

Installed reference monuments to the existing corner monument as follows:

A aluminum nail in the east side of PP&L Pole No. 324000, 1' above ground, bears N5°E 80.80'. Attached witness corner and bearing object sign to the pole.

A aluminum nail in the south side of PP&L Pole No. 055903, 1' above ground, bears N32°E 3.51'. Attached witness corner and bearing object sign to the pole.

U.S. Army Corps of Engineers Bench Mark No. K-306-1941-AIRPORT 1, a 3 1/2" brass disc set in the S.W. corner of a 11.5' by 11.5' concrete pad, bears S88°E 21.70'.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)