

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

T 2N, R 32E. , W.M.


Corner Code No. G-25

Note: Monument marked as shown below

**History of original corner establishment:**

This corner had been established and or re-established several times, in various surveys, prior to 1917.

In 1917, L.E. Wilkes, under Group 29 Instructions, recovered a 10 X 5 X 4 inch stone, marked 1/4 on West side and DR on East side and re-monumented it. Wilkes re-monumented the corner with a witness corner monument, a 3' long by 2' diameter iron post, set 1/2 link South of the corner point.



Corner No.  
Compass Declination: 18.0

**Description of corner evidence found:**

None. The corner area has been destroyed by a road cut.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

**Description of monument and accessories I established to perpetuate the original location of this corner:**

The corner was re-established by broken boundary methods as shown in the 1973 "Manual of Instructions", between the recovered West 1/4 corner and South 1 1/6 th corner of Section 7, T2N R33E, W.M..

Since corner point falls in a highway shoulder subject to construction, at a point S 00° 02' 10"E 60.00' from true corner point I establish a witness corner monument.

The witness corner is a 2 1/2" brass cap, marked as shown in corner diagram, set on a 1 1/4" by 30" galvanized iron pipe. The monument is set 24" in the ground and surrounded with a mound of earth and stone.

**Reference the witness corner monument as follows:**

The 1/4 corner monument on the West boundary of Section 7, T2N R33E, W.M. bears N 00° 13' 49"E 259.45'.

A concrete nail with brass washer, 1' East of the West edge of the pavement of the highway bears N 8 1/2° E 59.0'. The brass washer is stamped "PLS 1106".

A brass washer nailed to the South side of post for "Slower Traffic Keep Right" sign bears S 48 1/2° E 30.4'. The brass washer is stamped "PLS 1106" and is 5.5' above ground on the post.

A brass washer, 5.5' above ground, in PP&L Pole No. 129401, bears N 65° W 82.9'. The brass washer is stamped "PLS 1106". Attached bearing object sign to the pole.

Set steel fence post 3' South of corner and attached witness corner sign.

Office of *Survey Dept* County of *Wasatch*  
State of *OR* I hereby certify that the within instrument was filed in this office  
for record on the *July* day of *1977*  
*David H. Kumbier* by *Kathleen K. Amos*  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
Unsub. 68-10-100-207  
Date *7-90*  
Rec'd. *KA*  
No. *9A-571.0*