

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. J-13

Note: Monument marked as shown below


History of original corner establishment:

This corner was originally established by Daniel Chaplin, U.S. Deputy Surveyor, under Contract No. 107, dated September 21, 1864.

Z.F. Moody, U.S. Deputy Surveyor, in Contract No. 164, dated October 4, 1871, established a new corner. The Moody corner superceded the corner established by Daniel Chaplin.

Currin and Noland, U.S. Deputy Surveyors, under Special Contract dated May 4, 1887, recovered Moody's corner and re-monumented it.

This corner has been known and has been in continuous use for many years. It was re-monumented by City crews in past years and in 1988, was re-monumented with a brass capped iron pipe by PLS 933.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

2 1/2" brass cap on 1 1/4" galvanized iron pipe protruding 6" from the ground, in good condition. There is a old 2 1/2" iron pipe with old witness corner sign on it located S 35 E 1.4' from the corner monument. The monument is located 1.1' West of a North-South fence along the West side of Olney Cemetery.

Description of monument and accessories established to perpetuate the original location of this corner:

I reference the monument by PLS 933 as follows:

A brass washer stamped "PLS 1106" in the West side of PP&L Pole No. 099002, 0.5' above ground, bears S 23°W 2.71'. Attached bearing object and witness corner signs to the pole.
 The Northeast corner of a metal storm grate frame bears S 41°W 54.3'.
 The center of a phone pedestal bears N 27°W 2.1'.
 The center of a 3" dia. metal guard post, 1' East of the Northeast corner of the most Northerly stall of the car wash bears N 26°W 94.7'.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of Survey Dept. County of Umatilla
 State of OR, I hereby certify that the within instrument was filed in this office
 for record on the 19th day of July, 1990
David H. Robinson by Kathleen K. Amberg
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor ★GPO: 1989-692-049

Book 7-90
 Page 1A
 No. 90-50-C