

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. J-3


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by D. Chaplin, U.S. Deputy Surveyor, under Contract No. 107, dated August 21, 1864. The original notes state that at the corner a post was set.

In 1902, in County Survey No. 147, County Surveyor John Kimbrell retraced the Section line between Sections 7 and 18, but his notes are unclear as to whether he recovered the corner, or re-established it.

Survey No. 85-157-C implies a calculated position for this corner, but the calculated position is not shown on the map.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

None, other than an old North-South fence through the corner area.

Description of monument and accessories established to perpetuate the original location of this corner:

Re-established the corner on line between the re-established Southwest corner of Section 7 and the recovered Southeast corner of Section 7, using the long standing north-south fence to control the corner position longitudinally.

At the re-established corner point, set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe, 28" in the ground and surrounded with a mound of earth. From the re-established corner point:

A aluminum nail and brass washer in the East side of a wood post fence corner, 2' above ground, bears N 1° E 90.4'. Attached bearing object sign to post.
A aluminum nail and brass washer in the South side of a wood fence post in a fence line running S 63° W, 2' above ground bears N 30° W 83.1'. Attached bearing object sign to post.
The base of the 7th steel fence post South of the fence corner (fences go S 63° W and S 1° W) bears S 1° W 19.6'.
The base of the 8th steel fence post South of the fence corner noted above bears S 1° W 34.2'.

The brass washers are stamped "PLS 1106".

Set steel fence post 2' south of corner and attached witness corner sign.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of Survey Dept. County of Washtenaw

State of Ohio, I hereby certify that the within instrument was filed in this office

for record on the 10th day of July, 1977

David H. Kimbrell
(COUNTY OFFICIAL)

John P. Amstutz
(DEPUTY)

RECEIVED BY
Unit #1
Date: 7-90
File: RA