

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

T 2N, R 32E., W.M.

Corner Code No. J-5

Note: Monument marked as shown below

**History of original corner establishment:**


This corner was originally established by Daniel Chaplin, U.S. Deputy Surveyor, under Contract No. 107, dated September 21, 1864. The original notes state that at the corner a stone, 24 X 14 X 5 was set for the corner:

In County Survey No. 147, in 1902, John Kibrell, County Surveyor, recovered the corner.

Survey No. D-5-B, in 1967, indicates a stone found for the corner.

Survey No. D-4, in 1967, indicates a found stone which was replaced with a brass cap.

Survey No. 85-157-C, in 1985, indicates a brass cap found.



Corner No.  
Compass Declination: 18.0

**Description of corner evidence found:**

Stone of record size (no visible marks), in a mound of stone.

There is absolutely no evidence of a brass cap monument at this corner, as indicated on Survey No. D-4 and 85-157-C.

**Description of monument and accessories established to perpetuate the original location of this corner:**

At the position of the found original stone in stone mound, set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized pipe 20" in the ground to bedrock and surrounded with a mound of earth and stone. Buried corner stone in the new mound.

From the remonumented corner point:

- A 3' by 3' by 1' out of the ground rock outcrop bears N 54°W 21.1' marked "X B0" on Southeast top.
- A 1 1/2' by 1' by 1' out of ground rock outcrop bears S 79°E 33.2' marked "X B0" on West face.
- A 3' by 1 1/2' by 1 1/2' out of ground rock in place bears S 18°E 75.9' marked "X B0" on top.
- A 5' by 3' by 1 1/2' out of ground rock outcrop bears S 46°W 40.7' marked "X B0" on Southeast side.

There is no suitable reference object in the Northeast quadrant.

Set steel fence post South of corner and attached witness corner sign.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of Survey Dept. County of Umatilla  
State of OR, I hereby certify that the within instrument was filed in this office  
for record on the 19th day of July, 1977  
David H. Humberby (COUNTY OFFICIAL) William R. Wells (DEPUTY)

RECEIVED BY  
Umatilla County Surveyor  
Date 7-90  
By AT  
No. 90-57-10