

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. J-5

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Daniel Chaplin, U.S. Deputy Surveyor, under Contract No. 107, dated September 21, 1864. The original notes state that at the corner, a stone, 24 x 14 x 5 was set for the corner.


In County Survey No. 147, in 1902, John Kimbrell, County Surveyor, recovered the corner.

Survey No. D-5-B, in 1967, indicates a stone found for the corner.

Survey No. D-4, in 1967, indicates a found stone which was replaced with a brass cap.

Survey No. 85-157-C, in 1985, indicates a brass cap found.

In Survey No. 90-50-C, a stone in stone mound was recovered and re-monumented with a 2 1/2" brass cap on a 1 1/4" galv. iron pipe.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

2 1/2" brass cap on 1 1/4" galv. iron pipe, in stone mound, from which:

A 3' by 3' by 1' out of ground rock outcrop bears N 54°W - 21.1' marked "X B0" on Southeast top.

A 1 1/2' by 1' by 1' out of ground rock outcrop bears S 79°E - 33.2' marked "X B0" on West face.

A 3' by 1 1/2' by 1 1/2' out of ground rock in place bears S 18°E - 75.9' marked "X B0" on top.

A 5' by 3' by 1 1/2' out of ground rock outcrop bears S 46°W - 40.7' marked "X B0" on top.

Found a steel fence post 3' south of monument with a Witness Corner sign attached.

Description of monument and accessories established to perpetuate the original location of this corner:

From the found brass cap monument, these additional accessories were set:

A 5/8" by 30" iron pin bears N 41 1/2°W - 26.0' capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106".

A 5/8" by 30" iron pin bears N 30 1/2°E - 22.4' capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106".

A 5/8" by 30" iron pin bears S 64°E - 28.7' capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106".

A 5/8" by 30" iron pin bears S 51°W - 24.7' capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106".

Set a steel fence post, on rough line, approximately 1 foot from each pin with a Bearing Object sign attached.

REGISTERED PROFESSIONAL LAND SURVEYOR
---

*With: R. Wells*

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106
---

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 8-92  
Rec'd By KR  
No. 92-92-C

★ GPO-798-276