

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. L-1

Note: Monument marked as shown below


History of original corner establishment:

Corner originally established by Josiah A. Burnett under GLO Contract No. 92 dated September 12, 1860, and his record states:

"Set a post for 1/4 sec. cor. drove charred stake and raised mound as per instructions."

Corner re-established by Willard Bradley, County Surveyor, on April 22, 1916, as recorded in Book 2 at pages 284 thru 287 in the Record of Permanent Surveys of the Umatilla County Survey Records. At position determined by single proportion measurement between recovered adjacent section corners North and South his record states: "Set 1/4 corner stone 20'x7'x7' marked 1/4 on South and raised mound of stone."

The corner was recovered and re-monumented by W.L. Hanley in Survey No. 89-56-R.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

A 2 1/2" brass cap on 1 1/4" galv. iron pipe in a mound of stone from which:

An iron pin with an aluminum cap bears N70 1/2°W - 9.1'. (matches record)  
An iron pin with an aluminum cap bears N15 1/2°E - 20.00'. (matches record)

Steel fence posts with Witness Corner signs and Bearing Object signs attached near both pins.

There is a steel fence post with a Witness Corner sign attached East of the corner monument.

Description of monument and accessories established to perpetuate the original location of this corner:

Marked additional corner accessories as follows:

A 5/8" by 30" iron pin bears N 71 1/2°E - 21.59' capped with a yellow plastic cap marked "W.R. Wells, PLS 1106"  
A 5/8" by 30" iron pin bears S 35°W - 20.75' capped with a yellow plastic cap marked "W.R. Wells, PLS 1106".

Set a 5.5' steel fence post, on rough line, approximately 1 foot from each pin, with a Bearing Object sign attached.

REGISTERED PROFESSIONAL LAND SURVEYOR
<i>William R. Wells</i>
OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 8-92  
Rec'd By KR  
No. 92-92-C