

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. L-9

Note: Monument marked as shown below

History of original corner establishment:

Most recent approved GLO record, by Currin and Noland, under Special Contract dated May 4, 1887 states:

Set stone 9x8x7 ins. 6 ins. in the ground for 1/4 sec. cor. marked 1/4 on N. face dug pits 18x12 ins. N. & S. from stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high 3 ft. base around it.

A survey by W.E.O. Criger, dated March 1951, shows "I.P. found".

The "I.P." and marked stone were found and remonumented by James L. Chaffee, City Engineer in 1970. (Survey No. G-1026).

DIAGRAM

UMATILLA COUNTY
1/4 COR.
17:16
SURVEYOR

Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found 2 1/2" Brass cap set in concrete with a steel fence post 1.1' South.

Description of monument and accessories I established to perpetuate the original location of this corner:

From the existing monument:

A 5/8" by 30" iron pin bears N 0 1/2°W - 18.35' dist. with a yellow plastic cap marked "W.R. WELLS PLS 1106" attached.

A 5/8" by 30" iron pin bears N 84 1/2°E - 21.33' dist. with a yellow plastic cap marked "W.R. WELLS PLS 1106" attached.

A 5/8" by 30" iron pin bears S 2 1/2°E - 9.42' dist. with a yellow plastic cap marked "W.R. WELLS PLS 1106" attached.

Power pole no. 6/33 bears S 66°W - 3.89' dist. with a Brass washer stamped "W.R. WELLS PLS 1106" nailed to base of pole and Bearing Object sign attached.

Set a 5.5 foot steel fence post, on rough line, approximately 1 foot from each pin with a Bearing Object sign attached.

Placed witness corner sign on the steel fence post 1.1' South of corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 8-9-92

Rec'd By KK

No. 92-92-C