

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. N-13

Note: Monument marked as shown below


History of original corner establishment:

Most recent approved SLD record, by Currin and Noland, under Special Contract dated May 4, 1887 States:

"Intersect E. & W. line 20 lks. East of old corner to Secs. 15, 16, 21 & 22. Set stone 8x10 ins. in old mound for cor. to sections 15, 16, 21 & 22 marked with 3 notches on E. & S. edges. Redug pits 18x18x12 ins. in each Sec. 5 1/2 ft. dist. and raised a mound of earth 2 ft. high 4 1/2 ft. base alongside".

The City of Pendleton called for a fence corner in a survey dated January, 1936. (City Record 24-7309).

A 5/8" x 30" iron pin monument was set at the fence corner in 1983, after the fence corner location was verified by survey. (Survey No. 83-73-B).



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

A 5/8" by 30" iron pin on West edge of fence post at a East-West and South fence corner, set during Survey No. 83-73-B.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" by 30" galv. iron pipe over found iron pin. From the new monument:

- A 5/8" by 30" iron pin bears N 10°W - 26.50' capped with a yellow plastic cap marked "W.R. Wells, PLS 1106".
- A 5/8" by 30" iron pin bears N 87°E - 20.11' capped with a yellow plastic cap marked "W.R. Wells, PLS 1106".
- A 5/8" by 30" iron pin bears S 02°E - 20.00' capped with a yellow plastic cap marked "W.R. Wells, PLS 1106".
- A 5/8" by 30" iron pin bears S 87 1/2°W - 20.00' capped with a yellow plastic cap marked "W.R. Wells, PLS 1106".

Set a 5.5' steel fence post, on rough line, approximately 1 foot from each pin, with a Bearing Object information sign attached.

Set a steel fence post 3' West of monument with a Witness Corner sign attached.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by ..... (DEPUTY)  
 (COUNTY OFFICIAL)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 8-92  
 Rec'd By KK  
 No. 92-92-C