

RTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E. , W.M.

Corner Code No. N-17

Note: Monument marked as shown below


History of original corner establishment:

Most recent approved GLO record, by Currin and Noland, under Special Contract dated May 4, 1887, states:

"Found old mound and pits restored corner by setting a basalt stone 12x7x6 ins. 8 ins. in the ground marked with 3 notches on South and 2 notches on the East edges, re dug pits and raised a mound of earth 2 ft. high & 4 1/2 ft. base around it".

Note: We find no record of the establishment of the found brass cap monument by the City of Pendleton. The brass cap monument is believed to be a perpetuation of the hub set for the corner point by Charles Caddeman, during his survey in January, 1936. (City Map Record No. 24-7309).

Corner designation: T2N R32E
S15 | S14
S22 | S23



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found a 1 3/4" brass cap set in concrete 1.4' South of a East-West fence and 6" below ground surface.

Description of monument and accessories | established to perpetuate the original location of this corner:

Maintained by cleaning up around found monument. Referenced the existing monument with the following accessories:

- A 5/8" by 30" iron pin bears N 81°W - 16.55'.
A 5/8" by 30" iron pin bears N 76 1/2°E - 16.25'.
A 5/8" by 30" iron pin bears N 88°E - 20.23'.
A 5/8" by 30" iron pin bears S 84 1/2°W - 14.54'.

All iron pins are capped with a yellow plastic cap marked "W.R WELLS, PLS 1106"

Set steel fence posts approx. 1' from each pin and attached Bearing Object signs.

Set a steel fence post 2' North of monument and attached a Witness Corner sign.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
..... by .....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 8-92

Rec'd By KR

No. 92-92-C