

RTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.


Corner Code No. N-25

Note: Monument marked as shown below

History of original corner establishment:

Most recent approved GLO record, by L.E. Wilkes, U.S. Surveyor, under special instructions dated February 20, 1917 states:

Point for cor. of secs. 13 and 24 falls in road. At a point 45 1/2 ft. E. of cor. Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in ground, for witness cor. to the cor. of secs. 13 and 24, 1. 2 N., R. 32 E., with brass cap marked



Corner No. Compass Declination: 18.0°

Description of corner evidence found:

None. The witness corner monument has been farmed out. Re-established corner point by single proportion measurement between the S 1/16th corner of Section 18 and the West 1/4 corner of Section 19, T2N., R33E., W.M.. The West 1/4 corner of Section 19 has been removed since 1982. The position for the West 1/4 corner of Section 19 was calculated using Survey No. 82-50-B, which was performed by me in 1982.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" x 30" galv. iron pipe 42" in ground under the road.

A brass washer bears N 10°W - 164.7', and is nailed with an alum. nail to PP&L pole no. 13900.

A brass washer bears N 6°W - 236.9', and is nailed with an alum. nail to PP&L pole no 13960.

A 5/8" x 30" iron pin bears N 8°59' E - 157.9', and is capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106". Set a steel fence post by pin with a Bearing Object sign attached.

A brass washer bears S 9°W - 168.0', and is nailed with an alum. nail to power pole no. 4/5.

Brass washers are stamped "PLS 1106", with Bearing Object signs nailed near each washer.

Set a steel fence post East of monument and attached a Witness Corner sign.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of..... State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19....

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 8-92

Rec'd By [Signature]

No. 92-92-C