

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

T 2N, R 32E., W.M.

Corner Code No. P-17


Note: Monument marked as shown below

**History of original corner establishment:**

Corner was originally established by Daniel Chaplin, under Contract No. 107, dated September 21, 1864. Set 18" x 10" x 10" stone for corner.

Corner was reset by Zenas F. Mopdy, under Contract No. 165, dated October 4, 1871. Set 18" x 16" x 1" stone for corner.

Corner was reset by Jas. P. Currin and Jas. Moland, under Special Contract, dated May 4, 1887. Set a stone 20" x 14" x 8" in the ground 1/4" for the corner, marked 1/4 on the West face, redug pits North and South of stone and raised mound of earth alongside.



Corner No.  
Compass Declination: 18.0°

**Description of corner evidence found:**

1 inch octogon bar at projection of a North-South fence and an East-West fence.  
Survey references to this monument:  
Hayes and Harris, dated 5/16/60, as iron pin. Map No. Q-452-A.  
Ralph Thompson, dated 5/2/73, as setting brass cap. Map No. H-220-Ax.  
Ralph Thompson, dated 3/16/76, found 3/4" iron pin. Map No. L-67-A.

**Description of monument and accessories established to perpetuate the original location of this corner:**

Set: a 2 1/2" brass cap on 1 1/4" x 30" galv. iron pipe 32" in ground.  
(Buried octogon bar in mound).  
Attached a Witness corner sign to fence post (gate post) 8.0 feet East.  
New bearing objects:  
A brass washer nailed to gate post, 1 foot above ground, bears N 87° E - 8.0 feet.  
A brass washer nailed to a power pole, 1 foot above ground, bears S 75° E - 47.1 feet.  
A brass washer nailed to a power pole, 1 foot above ground, bears S 01° W - 63.3 feet.  
A brass washer nailed to a fence corner post, 1 foot above ground, bears West - 42.6 feet.

Brass Washers are stamped "PLS 1106". Bearing Object signs are nailed above the brass washers.

REGISTERED PROFESSIONAL LAND SURVEYOR
---------------------------------------------

*William R. Wells*

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106
-----------------------------------------------------

*Expires 12/31/94*

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)