

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. P-5


Note: Monument marked as shown below

History of original corner establishment:

Corner was originally established by Daniel Chaplin, under Contract No. 107, dated September 21, 1864. At that time he set a wooden post in a mound of earth with a charred stake, pits and etc. as per instructions.

Corner was referred to by Krumbein Engineering Co., on Map No. R-28-B, but was not re-established at that time.

J. W. Kimbrell, in Record of Private Surveys, Book 1, Page 487, claims to have reestablished the corner, but does not indicate what type of corner monument was set.



Corner No.

Compass Declination: 18.0°

Description of corner evidence found:

A 5/8" iron pin was found 23.28 feet North (on line) from the calculated and referenced position of the 1/4 corner, as referred to on Krumbein Engineering Co.s Map No. R-28-B.

Corner was re-established by single proportion measurement between the Southwest and Northwest corners of Section 20.

Description of monument and accessories established to perpetuate the original location of this corner:

At position determined by survey:

- A 2-1/2" dia. brass cap on a 1-1/4" x 30" galv. iron pipe 30" in the ground, marked as noted in the corner diagram, from which we set:
 - A steel fence post, 3.0 feet North, with a Witness corner sign attached.
 - A 5/8" x 30" iron pin bears N 14° W - 33.4 feet
 - A 5/8" x 30" iron pin bears N 24° E - 46.8 feet
 - A 5/8" x 30" iron pin bears N 73° E - 23.3 feet
 - A 5/8" x 30" iron pin bears N 60° W - 2.7 feet
 - A 5/8" x 30" iron pin bears N 00° 28' 44"W - 23.28 feet (From Map No. R-28-B).
- All iron pins have plastic caps stamped "WR WELLS - PLS 1106". Bearing Object signs are wired to each pin.

REGISTERED

PROFESSIONAL

LAND SURVEYOR

William R. Wells

OREGON

JULY 22, 1977

WILLIAM R. WELLS

1106

expires 12/31/94

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)