

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 07/27/07

CORNER DESIGNATION: 2N32, T5. The West One-Quarter Corner of Section 29.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was originally established by Daniel Chaplin under Contract No. 107, dated September 21, 1864. Original Notes state: "Set post for 1/4 Sec. Corner".

At Record of Private Surveys, Book 1, Page 317, John Kimbrell shows a plat of Section 29, indicating he partly subdivided Section 29 and apparently recovered the West One-Quarter Corner. Kimbrell's plat does not indicate what was found for the corner, but he must have recovered it because he subdivided the Southwest Quarter of the Section, and reported a distance of 79.84 chains between the East and West One-Quarter corners of the Section.

The map of the Pilot Rock Branch line of the OWR & N Co. shows a distance tie to the corner, from track centerline, of 943 feet.

MONUMENT AND ACCESSORIES FOUND: I found a basalt stone, 8" x 8" x 16", lying on top of two other basalt stones embedded in the ground, in the form of a mound, at the Southerly end of a old field berm extending North. There was another stone, 20" x 10" x 8", lying loose, 5 feet East of the mound. No marks were found on any of the stones. These were the only stones in the immediate area. I accept the center of the stone mound as best remaining evidence of the original corner location. From the mound, there are old piles of rock from an old fence now removed, extending East about 700 feet to the top of a ridge and South, about 400 feet, to a draw. The fence remains East and South are along the lines surveyed by Kimbrell in his survey plat reported in Record of Private Surveys Book 1, Page 317. Also found fragments of old wood fence post in the mound. The distance from the accepted mound to the centerline of the Pilot Rock Branch line is 941 feet, by resource grade GPS tie with Trimble Pro XR.

MONUMENT MARKING DETAIL:

T2N R32E
1/4
S30|S29
2007
PLS 1106

MONUMENT SET:

At the center of the accepted mound of stone, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe, 20" in the ground to bedrock and surrounded with a mound of earth and stone.

New accessories:

A 5/8" by 24" rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears N 08°E, 34.0', with bearing object sign attached.

A 5/8" by 24" rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears S 66°E, 55.4', with bearing object sign attached.

A 5/8" by 24" rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears S 18°W, 49.7', with bearing object sign attached.

A 5/8" by 24" rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears N 82°W, 30.0', with bearing object sign attached.

LOCATION AND COMMENTS: Corner is located on a West facing hillside, 800 feet South of Birch Creek Road.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 717847.62

E = 8624619.60

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East
Witnesses: Jason Wells, LSIT

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

2N32T5

RECEIVED BY

Umatilla County Surveyor

Date 8-07

Rec'd By KF