

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/14/94

CORNER DESIGNATION: V-11. North 1/4 corner Section 33, T2N., R32E., W.M..

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. NOTE - Currin and Noland field notes do not state that the 1/4 corner was recovered or re-established.

MONUMENT AND ACCESSORIES FOUND: None. Corner is located in an active wheat field.

MONUMENT MARKING DETAIL:

T2N R32E
 S28
1/4 ———→
 S33
 1994
 PLS 1106

MONUMENT SET: Corner was re-established by single proportion measurement between the Northwest and Northeast corners of Section 33. At position determined by survey, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, buried 42" in the ground, (marked as shown in monument detail).

New Accessories:

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 43° E-21.9 feet, top set 1.2 feet below ground.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 43° E-94.3 feet, set flush with ground at existing fence post base.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 41 1/2° W-81.7 feet, set flush with ground at existing fence post base.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 41° W-25.0 feet, top set 1.2 feet below ground.

Attached bearing object sign to each iron pin. Attached witness signs to existing steel fence posts for reference monuments in the Southwest and Southeast quadrants.

LOCATION & COMMENTS: Corner falls in active wheat field.

COMPASS DECLINATION: 18° East.

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Surveyor's Seal

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JUL 25 1977
WILLIAM R. WELLS
1106

renews 12-31-96