

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/14/94

CORNER DESIGNATION: V-21. Northeast corner Section 35, T2N., R32E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. They recovered old corner and set a stone 20 x 12 x 8 ins., 14 inches in the ground marked with 1 notch on E. and S. edges; re-dug pits 18 x 18 x 12 ins., in each section 5 1/2 ft. distant from stone and raised a mound of earth 2 ft. high, 4 1/2 ft. base over it. This corner was re-established by PLS 1280 in 1982 in Umatilla County Survey No. 82-51-C.

MONUMENT AND ACCESSORIES FOUND: Found 3" brass cap on galvanized iron pipe set 14" below ground, per Umatilla County Survey No. 82-51-C. This corner monument was rejected because it was established using the Daniel Chaplin rather than Currin and Noland GLO record.

MONUMENT MARKING DETAIL:

T2N	R32E
S26	S25
S35	S36

1994
PLS 1106

MONUMENT SET: Corner position was re-established by double proportion measurement between the Northwest corner of Section 35, the Southeast corner of Section 25, the Northeast corner of Section 26, and the Southeast corner of Section 35, using the Currin and Noland record. At the re-established corner position, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 42" in the ground, (marked as shown in the monument detail). The rejected monument by PLS 1280 bears S 60°16' E - 5.8 feet.

New Accessories:

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 52° E-22.4 feet, top set 1.2 feet below ground.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 40° E-24.7 feet, top set 1.2 feet below ground.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 26° W-19.7 feet, top set 1.2 feet below ground.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 41 1/2° W-12.7 feet, top set 1.3 feet below ground.

Attached bearing object signs to each pin.

LOCATION & COMMENTS: Corner falls in farmed Conservation Reserve Program field.

COMPASS DECLINATION: 18° East.

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Surveyor's Seal

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 23, 1977
WILLIAM R. WELLS
1106