

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/14/94

CORNER DESIGNATION: V-23. North 1/4 corner Section 36, T2N., R32E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. They found old 1/4 sec. corner and reset stone 16 x 8 x 4 ins., 10 inches in the ground for 1/4 Sec. corner. Marked 1/4 on N. face and re-dug pits 18 x 18 x 12 ins. E. & W. from stone, 5 1/2 ft. distant, and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.

MONUMENT AND ACCESSORIES FOUND: None

MONUMENT MARKING DETAIL:

T2N R32E  
S25  
1/4  
S36  
1994  
PLS 1106

MONUMENT SET: Re-established corner by single proportion measurement between the Northwest and Northeast corners of Section 36. At re-established corner position, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 44" in the ground, (marked as shown in the monument detail).

New Accessories:

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 38° E-15.6 feet, top set 1.1 feet below ground.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 28 1/2° E-18.3 feet, top set 1 foot below ground.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 41° W-16.8 feet, top set 1.3 feet below ground.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 35° W-20.4 feet, top set 1.1 feet below ground.

Attached bearing object signs to each iron pin.

LOCATION & COMMENTS: Corner falls in farmed Conservation Reserve Program field.

COMPASS DECLINATION: 18° East.  
FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Surveyor's Seal

Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

renews 12-31-94

RECEIVED BY

Umatilla County Surveyor

Date 8-94

Rec'd By KK

No. 24-109-C