

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/22/94

CORNER DESIGNATION: X-21. East 1/4 corner Section 35, T2N., R32E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. They set a stone, 16 X 10 X 6 ins., 10 ins. in the ground for 1/4 Sec. corner. Marked 1/4 on W. face. Dug pits 18 x 18 x 12 ins. N. & S. from stone 5 1/2 ft. distant and raised a mound of earth 1-1/2 ft. high, 3-1/2 ft. base over it. This corner was re-established by PLS 1280 in 1982 per Umatilla County Survey No. 82-51-C.

MONUMENT AND ACCESSORIES FOUND: Found 3" brass cap on galvanized iron pipe set 15" below ground per Umatilla County Survey No. 82-51-C. This corner monument was rejected because it and other controlling corners were established using the Daniel Chaplin rather than the Currin and Noland GLO record.

MONUMENT MARKING DETAIL:

T2N R32E
1/4
|
S35 . S36
|
1994
PLS 1106

MONUMENT SET: Corner position was re-established by single proportion measurement, using the GLO record by Currin and Noland, between re-established or recovered corners at the Northeast and Southeast corners of Section 35. At re-established corner position, set a 2 1/2" brass cap on 1 1/4" x 30" galvanized iron pipe, 42" in ground, (marked as shown in the monument detail). The rejected monument by PLS 1280 bears S 61°24' E - 2.9 feet.

New Accessories:

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 40 1/2° E-39.3 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 45° E-26.6 feet.
Power pole with a brass washer stamped "PLS 1106", nailed to it, bears S 64° W-40.3 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372", bears N 48 1/2° W-47.9 feet.
Attached bearing object signs to iron pins and above brass washer.
Set steel fence posts near iron pins with witness signs attached.

LOCATION AND COMMENTS: Corner falls in farmed Conservation Reserve Program field.

COMPASS DECLINATION: 18° East
FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 2, 1977
WILLIAM R. WELLS
1105

1000ws 12-21-94