

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


T 2N , R 32E. , W.M.

Corner Code No. Z-1

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Josiah A. Burnett, Deputy Surveyor, under Contract No. 92, dated September 12, 1960. Set post and drove charred stake, raised mound and trenches, as per instructions.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

Found remnants of a charred stake 18" below the ground at the intersection of an ancient fences extending East-West and North. The charred stake remains may be part of an old fence post. The fence extending West is straight and visible for several miles. We also found a rock mound in the fenceline 1/2 mile to the East.

The fence corner was accepted as the best remaining evidence of the original Township Corner location.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" x 30" galv. iron pipe, 27 inches in the ground with a mound of stone to the cap.

Attached a Witness corner sign to the corner post of the fence intersection 0.5 feet North of the monument.

New Bearing Objects:

- A 5/8" x 30" iron pin bears N 06° W - 15.2 feet. (Flush with the ground).
- A 5/8" x 30" iron pin bears N 81° E - 19.5 feet. (Flush with the ground).
- A 5/8" x 30" iron pin bears S 19° E - 24.1 feet. (Buried 16 inches).
- A 5/8" x 30" iron pin bears S 82° W - 16.4 feet. (Flush with the ground).

All iron pins are capped with a 1 1/2" yellow plastic cap, marked: "WR WELLS, PLS 1106". Bearing Object signs are wired to each pin.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*expires 12/31/94*

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)