

**PUBLIC LAND CORNER CONDITION REPORT**

**UMATILLA COUNTY, DATE: 11/15/01**

**CORNER DESIGNATION: 2N33, E-1, The Southwest corner of Section 6 only.**

**PREVIOUS RENEWALS/ SURVEYS, ETC..:**

Corner was remonumented in 1988 Dependent resurvey by BLM recored in the Umatilla County Surveyor's Office.

**MONUMENT AND ACCESSORIES FOUND:**

Found a 3" brass cap on stainless steel pipe monument, cap 2" above ground level, marked as shown in monument marking detail. Per BLM record, the corner has 2 accessories. We did not dig up the deep-1 magnet.

**MONUMENT MARKING DETAIL:**

US DEPT. OF THE INTERIOR  
US BUR OF LAND MANAGEMENT

T2N  
R32E|R33E  
S1 | S6 C  
| S7 C  
1988

**LOCATION & COMMENTS:**

Corner is located 3 feet West of North/South fenceline in pastured field.

**STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD83/91, INT. FOOT:**

N = 737100.09  
E = 8650559.63

**FIRM/AGENCY:** William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

2N33E1

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02*

RECEIVED BY

Umatilla County Surveyor

Date 12-01

Rec'd By KK

File 01-211-9