

PUBLIC LAND CORNER CONDITION REPORT

UMATILLA COUNTY, DATE: 01/02/02

CORNER DESIGNATION: 2N33E5, The Northeast Corner of Section 7.

PREVIOUS RENEWALS/ SURVEYS, ETC.:

Corner monumented by BLM in 1988, under recorded survey notes by Richard L. Johnson, Cadastral Surveyor.

MONUMENT AND ACCESSORIES FOUND:

Found a 3" brass cap on 2 1/2" stainless steel post protruding 4" above ground level in small mound of earth marked as shown in monument marking detail.

The four bearing tree accessories by BLM are intact with visible scribes but the SW and NW bearing trees are dead.

MONUMENT MARKING DETAIL:

U.S. DEPT. OF
INTERIOR
T2N R33E
6 | 5
7 | 8
1988
BLM

LOCATION & COMMENTS:


Located on North side of Umatilla River in flat area South of rim rock cliff.

STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD83/91, INT. FOOT:


N = 737249.75
E = 8655614.00

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

\2N33E5



William R. Wells



renews 6-30-02

RECEIVED BY

Umatilla County Surveyor

Date 2-02

Rec'd By KK

No. 02-43-9