

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 01/09/03

CORNER DESIGNATION: N-1, the Northwest Corner of Section 19 only, T2N, R33E, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was most recently re-established by L.E. Wilkes, under Special Instructions, Group 29, dated Feb. 20, 1917. Notes state: Point for closing corner of Secs. 18 and 19 falls in road. At a point 45 1/2 lks. E. of cor. Set a iron post, 3 ft. long, 2 ins. diam., 24" in the ground for witness cor. to closing cor. of secs. 18 and 19 T2N., R33E., with marked brass cap.

MONUMENT AND ACCESSORIES FOUND: None. The Wilkes witness corner monument has been destroyed by road building.

MONUMENT MARKING DETAIL:

T2N  
R32E R33E  
| S18  
S13 | -----CC  
| S19  
2003  
PLS 1106

MONUMENT SET:

Corner position was determined by proportional measurement using ties and measurements to the corner monuments reported on Survey Nos. 93-054-C and 92-092-C. The corner point falls in Goad Road. Set a 2 1/2" brass cap on 1 1/4" by 30" galv. iron pipe with cap buried 8" below road surface. Cap is marked as shown on "Monument Marking Detail".

Accessories:

The section corner applying to sections 13 and 24 only, T2N., R32E., W.M., bears S 00°03'17" E., 180.28'.  
A 5/8" rebar with yellow plastic cap marked "WR Wells, PLS 1106" bears S 42 1/2° E., 34.6'.  
Wired "bearing object" sign to steel fence post just North of rebar. This rebar is also an accessory for the section corner applying to sections 13 and 24 only.  
The center of a telephone pedestal bears N 18°E., 64.2'.  
A 3/4" brass washer stamped "PLS 1106", nailed 2 feet above ground on the South side of a sawn off power pole 4 feet high bears S 56°W., 30.4'. Nailed "bearing object" sign to the sawn off power pole.

LOCATION AND COMMENTS:

Corner falls near centerline of Goad Road. There is also a 8 foot wide road extending East from corner point. This section corner applies to Sections 18 and 19, T2N., R33E., W.M., only.

STATE PLANE COORDINATES, OREGON NORTH NAD 83(91), International Feet:

N = 726456.66  
E = 8650778.70

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\2N33N1

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Wells - R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-04*

RECEIVED BY

Umatilla County Surveyor

Date 3-03

Rec'd By KE

No. 03-51-9