

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 09/05/97

CORNER DESIGNATION: N-11, The North Quarter Corner of Section 21.

PREVIOUS RENEWALS/SURVEYS ETC.: None, since survey by C.E. Redfield.

MONUMENT MARKING DETAIL:

T2N R33E

1 S16

4 S21

1997

PLS 1106

MONUMENT SET:

Re-established corner point by single proportionate measure between the Northeast and Northwest corners of Section 21, using the C.E. Redfield record.

Set a 2 1/2" brass cap on a 1 1/2" x 30" galvanized iron pipe, 24" in the ground, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears N 81° E, 8.65 feet.

A brass washer, 0.5 feet above ground, stamped "PLS 1106" bears S 48° E, 7.25 feet from West face of guard rail post.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears S 79° W, 2.62 feet.

A brass washer, 0.5 feet above ground level, stamped "PLS 1106" bears N 45° W, 4.70 feet. Brass washer is attached to East face of guard rail post.



All iron pin bearing objects have tags and fence posts nearby with survey marker signs attached.

LOCATION AND COMMENTS: Corner is located by guard rail barricade, just North of Freeway fence.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: John Linder, LSIT
Jason Wells



renews 6-30-98

RECEIVED BY
Umatilla County Surveyor
Date 11-97
Rec'd By JK
No. 97-222-C