


History of original corner establishment:
 L.E. Wilkes, U.S. Surveyor, reports recovering the corner during his surveys for the survey of Section 10, in 1917. Wilkes' 1917 survey was made under Group 29 Instructions dated September 5, 1917.
 C.E. Redfield's records indicate the corner was found when making his surveys in the area between 1917 and 1920.



Corner No.
 Compass Declination: 18.0°

Description of corner evidence found:

Farming and a large ditch has removed all evidence of the original corner.

Re-established corner by double proportion measurement between the re-established Southwest Corner of Section 15, recovered Southeast Corner of Section 14, recovered North 1/16th corner common to Sections 26 and 27 and re-established Northwest corner of Section 14. C.E. Redfield's record was used for proportioning to the North, South and East. No Redfield record was found for the South line of Section 15, so the record by Currin and Noland was used for proportioning to the West. Currin and Noland were the U.S. Deputy Surveyors who established the Southeast corner of Section 15 in 1887, under their Special Contract to subdivide sections on the Umatilla Indian Reservation.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe with top of pipe buried 6" below ground surface.

- Bearing Objects to corner:
 A 5/8" by 30" iron pin bears N 57 1/2° - 20.2'.
 A 5/8" by 30" iron pin bears S 34°W - 28.4', top 6" below ground surface.
 A 5/8" by 30" iron pin bears S 08 1/2°E - 34.8'.
 A 1/2" by 15" iron pin bears N 84°E - 79.3'.

5/8" pins are capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106".

All pins have a Bearing Object sign wired on, and are buried with top of pin at least 12" below ground surface unless otherwise noted.

Set an 8' steel fence post 1.3' North of monument, and attached a Witness Corner sign.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

expires 12-31-94

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

93-53-C