

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/09/03

CORNER DESIGNATION: P-5, the East One-Quarter Corner of Section 19, T2N, R33E, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was most recently established by Currin and Noland under Special Contract dated May 4, 1887. Currin and Noland notes call for a charred stake, with pits and mound and a scribed stake. This corner was likely recovered or re-established by C.E. Redfield, U.S. Indian Service Survey in around 1918. I find no notes for the Redfield recovery or re-establishment. BPA transmission line maps, dated 1950, call for a marked stone at the corner, in an East-West fence line.

MONUMENT AND ACCESSORIES FOUND: None. The corner point falls at the West edge of a North-South Road. Stone called in 1950 BPA survey has been destroyed by road building.

MONUMENT MARKING DETAIL:

T2N R33E
1/4
S19 | S20
2003
PLS 1106

MONUMENT SET:

There is a fence line extending East, beginning about 63 feet East of Corner point. Held location of fence extending East for latitude. Positioned corner at intersection of a line between the NE Corner of Section 19 and the recovered South 1/16th Corner common to Sections 19 and 20, and a line between the fence corner and West one-quarter Corner on the West line of Section 19. Position matches BPA call distance to the West one-quarter Corner of Section 19 by about two feet. Set a 2 1/2" brass cap on 1 1/4" by 30" galv. iron pipe with cap buried 14" below gravel road surface. Cap is marked as shown on "Monument Marking Detail".

New Accessories:

- A 3/4" brass washer stamped "PLS 1106", nailed to the West side of a power pole 1' above ground bears N 28° E., 46.1'. Nailed "bearing object" sign to the power pole.
- A 5/8" by 24" rebar, with yellow plastic cap marked "OR PLS 1106 WA PLS 17372" bears East., 63.4'. Wired "bearing object" sign to the rebar. This rebar is at the West end of a fence line extending East.
- A 3/4" brass washer stamped "PLS 1106", nailed 3 feet above ground to the East side of the Southerly pole of a set of 2 BPA power poles, bears S 52 1/2° W., 155.1'. Nailed "bearing object" sign to the power pole.
- A 3/4" brass washer stamped "PLS 1106", nailed 3 feet above ground to the East side of the Northerly pole of a set of 2 BPA power poles, bears S 57 1/2° W., 143.2'. Nailed "bearing object" sign to the power pole.

LOCATION AND COMMENTS:

Corner falls on the West edge of a 14' gravel road extending North-South.

STATE PLANE COORDINATES, OREGON NORTH, NAD 83(91), International feet:

N = 723885.79
E = 8655902.43

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
V2N33P5

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-04

03-51-9