

**PUBLIC LAND CORNER CONDITION REPORT**

**UMATILLA COUNTY, DATE:** 03/06/02

**CORNER DESIGNATION:** 2N33V13, the Northeast Corner of Section 33.

**PREVIOUS RENEWALS/ SURVEYS, ETC..:**

Most recent Umatilla County Surveyors recorded corner record: H-187

**MONUMENT AND ACCESSORIES FOUND:**

Found a 2 1/2" brass cap, 1" below paving in intersection of South Market Road and Lloyd Road, cap is unreadable. Found two brass cap witness monuments, one located at N 30° W, 60.00 feet, which is leaning Southeast with a steel fence post and witness post sign attached, and one located at N 30° E, 60.00 feet, flush with the ground with a steel fence post with witness post sign attached, both marked as shown in monument marking detail.

**MONUMENT MARKING DETAIL:**

Witness monuments:

UMATILLA COUNTY  
SURVEYOR  
T2N 28|27  
R33E 33|34  
WC  
N 30° W  
60.00 FT

UMATILLA COUNTY  
SURVEYOR  
T2N 28|27  
R33E 33|34  
WC  
N 30° E  
60.00 FT

**LOCATION & COMMENTS:**

Corner located at intersection of South Market and Lloyd Road.

**STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD83/91, INT. FOOT:**

Corner location:

N = 716092.32  
E = 8666724.47

**FIRM/AGENCY:** William R. Wells  
P.O. Box 1696  
Pendleton, Oregon 97801

2N33V13

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6/30/02*

RECEIVED BY

Umatilla County Surveyor

Date 5-02

Rec'd By KK

No. 02-123-9