

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Corner to Sections 1, 2, 11 and 12, T.2N, R.34E., WM.

Index: E-21


History of original corner establishment:

Corner originally set by Currin & Nolan special contract dated May 1887. His record reads: Set stone 14x12x8 for corner 1, 2, 11, and 12.

In 1919, Redfield replaced this stone with a brass capped monument.

In 1971, under Umatilla County Survey I-135-B, David Krumbain tied the following Redfield monuments to the Section Corner. The 1/4 corner common to Sections 1 & 2 and the south 1/16 corner common to Sections 1 & 2.

DIAGRAM



Evidence Found: None. A road constructed along the section line probably removed Redfield's monument. Found the above 1/4 and 1/16 corners.

Description of monument and accessories I established to perpetuate the original location of this corner:

Using Redfield's monuments and Krumbain's filed record of survey I-135-B as references, I set a 1" iron rebar with a 2" aluminum cap stamped as shown in the diagram above. The top of the cap was set flush with the ground. The monument is south and west of a of a broken down fence rock crib in the road at the base of the cut slope.

From which:

- An iron rebar bears N00°15'E, 68.52' immediately uphill of a steel fence post;
  - An iron rebar bears N83°45'E, 96.57' in an old rock jack stone mound;
  - An iron rebar bears S10°35'E, 48.29' at the northeast corner of a watering trough;
  - An iron rebar bears S45°34'E, 153.89' in a stone mound with fence post immediately uphill from the road.
- Each rebar is 5/8" x 24" and has a 2 3/8" diameter red plastic cap, stamped ORLS0852 and WAL513922.

The bearings are true.

This work was done November 19, 1999.

Office of \_\_\_\_\_ County of \_\_\_\_\_  
 State of \_\_\_\_\_, I hereby certify that the within instrument was filed  
 in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_.  
 \_\_\_\_\_ by \_\_\_\_\_  
 ( COUNTY OFFICIAL ) ( DEPUTY )

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*David L. Haddock*

OREGON  
 JULY 12, 1968  
 DAVID L. HADDOCK  
 352

RECEIVED BY  
 Umatilla County Surveyor  
 Date 11-99  
 Rec'd By KK  
 No. 99-281-B