

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 12/29/97

CORNER DESIGNATION: G-1. West 1/4 corner of Section 9, T2N., R34E., W.M..

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey record is that of Currin & Noland, GLO Surveyors, under Special Contract dated May 4, 1887. Record states:

"Deposited charred stake 12 ins. in the ground for 1/4 sec. cor.; dug pits 18 x 18 x 12 ins. N. & S. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in the N. pit drove stake 2 ft. long 2 ins. square, 12 ins. in the ground marked 1/4 S on W. face."

MONUMENT AND ACCESSORIES FOUND:

Found 15 inch long spike buried 1 ft. below road surface, near West edge of road, in line with fence extending West. Origin of spike is unknown.

MONUMENT MARKING DETAIL:

T2N R34E
1/4
S8 | S9
1997
PLS 1106

MONUMENT SET:

At position of found spike, set a 1 1/4 inch by 30 inch galvanized iron pipe with 2 1/2 inch brass cap, 38 inches in the ground (cap buried 8 inches below road surface), marked as show in Monument Marking Detail.

New accessories:

A brass washer nailed to a railroad tie fence post, 1 ft. above ground bears a grid azimuth of 352°50' a distance of 30.4 ft.

A 5/8 inch by 30 inch iron pin with 1 1/2" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" bears a grid azimuth of 52°36' a distance of 50.1 ft. (Top is buried 18 inches below farmed field).

A 5/8 inch by 30 inch iron pin with 1 1/2" yellow plastic cap marked "OR PLS 1106 WA PLS 17372" bears a grid azimuth of 119°07' a distance of 49.7 ft. (Top is buried 18 inches below farmed field).

A brass washer nailed to a railroad tie fence corner, 1 ft. above ground bears a grid azimuth of 271°45' a distance of 4.1 ft.

Brass washers are 3/4 inch in diameter and are stamped PLS 1106. Nailed witness corner and bearing object signs to the railroad ties where the brass washers are nailed. Attached bearing object signs to the buried iron pin accessories with wire.

LOCATION & COMMENTS:

Corner is located on West side of Whyte Road, 4 ft. East of a fence corner with fences extending South and West. Rotate grid bearings + 01°22' (clockwise) to convert to true bearing at corner point.

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Witnessed by: Jason Wells and Ben Weinke
RECEIVED BY

Will R. Wells

Umatilla County Surveyor

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Date 1-98

Rec'd By KK

No. 98-03-B

RENEWS 6-30-98