

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/26/98

CORNER DESIGNATION: J-13, The Southeast Corner of Section 9, T2N., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Most recent approved GLO Survey record is that of Currin and Noland, under Special Contract dated May 4, 1887. Record states: Set basalt stone 18 x 12 x 8 ins., 12 ins. in the ground for cor. to secs. 9, 10, 15 & 16, marked with 4 notches on S. and 3 notches on E. edges; dug pits 18 x 18 x 12 ins. in each sec. 5 1/2 ft. dist. and raised mound of earth 2 ft. high, 4 1/2 ft. base over it.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N R34E  
S9 | S10  
S16 | S15  
1998  
PLS 1106

MONUMENT SET:

After thorough search, I determined the best remaining evidence of the corner location is the intersection of a three way road intersection with roads extending North, West and South. At reestablished corner position:

Set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe 6" below gravel road surface.

Accessories set:

A 5/8" x 30" iron rod with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" flush with ground bears, N 26° E, 45.3 feet.

A brass washer stamped "PLS 1106", 1.0 feet above ground in a UECA guy pole bears S 52° E, 31.2 feet.

A brass washer stamped "PLS 1106", 1.0 feet above ground in UECA power pole #169900 bears S 35° W, 22.8 feet.

The Burke Road road sign pole bears N 13° W, 33.5 feet.

All accessories have bearing object signs attached.

5/8" pin has steel fence post 1.0 feet beyond with witness sign attached.

LOCATION AND COMMENTS:

See accompanying Record of Survey No. 98-

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: John Linder, LSIT  
Jason Wells

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

renews 6-30-2000

RECEIVED BY

Umatilla County Surveyor

Date 7-98

Rec'd By RR

No. 98-138-B