


J-9

1. T 2N R37E No. 5-9 Cor. NE Mer. W State Oregon N.F. #11 Umatilla Dist. #3 Pendleton

2. Corner Status



3. Original Description _____ Vol. _____ Page _____ Where recorded County Court House

4. Description of Corner: Basalt stone, 10x12x18 in. 10 in. in ground
Bearing Trees: Marked with 4 notches on E. and 4 notches on S.
Fir, 12 in. diam. bears N73°E 10 Lks. marked T2N, R37E; S 9 BT.
Fir, 29 in. diam. bears S62°E 28 Lks. marked T2N, R37E; S 16 BT.
Tamarack, 28 in. diam. bears S83°W --Lks. marked T2N, R37E; S BT.
~~#####~~ Bearing Trees cont'd:
Fir, 11 in. diam. bears N24°W 53 Lks. marked T2N, R37E; S 8 BT.

7. PHOTO IDENTIFICATION

Photo No. DVD-7M-37
Ident. By: _____

8. Plane Coordinate Position Data

State _____ Zone _____
 X _____
 Y _____
 Est. By _____
 Field Book No. _____
 Where Filed _____

9. EVALUATION

Authentic _____
 Needs Verif. Manum. No
 Re-Est. _____ Survey _____
 Land Status _____

5. Investigation notes: The Tamarack Bearing Tree has been found with the scribing in plain view. One of the Firs has been found, but it's bearing from the corner has not been established. As the legal description was not available at the time of investigation, the stone has not been searched for.

6. Signed R. A. Nelson Title Forester Date 2-21-61

PERPETUATION RECORD

10. MONUMENT:

11. ACCESSORIES

Field Book _____ Page _____

12. Set By _____ Title _____

License _____ Agency _____ Date _____

13. Recorded By _____ (Agency) _____ Volume _____ Page _____

(Date) (City) (County) (State)

14. REMARKS:

1 J-9