


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:
Corner not previously established.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Corner not previously established.

Description of monument and accessories I established to perpetuate the

original location of this corner: At a point on the Wilderness Boundary line at an Elevation of 4600 feet, I set a 2½" x 30" aluminum pipe with aluminum cap marked as shown, 28 inches in the ground, from which:

New Bearing Objects:


- A 5/8"x30" iron pin with plastic cap marked BGA SURVEY MARKER bears S78°W, 8.75 feet
- A 5/8"x30" iron pin with plastic cap marked BGA SURVEY MARKER bears N18°W, 6.98 feet

Raised a small mound of stone around monument.

Set a steel fencepost approximately 5 feet Southerly with Land Survey Monument and Wilderness Boundary signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on July 25, 1991.

Witness: Jim Bennett



**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Signature of Duane I. Griffith

OREGON
JULY 10, 1964
DUANE I. GRIFFITH
644

I used a steel tape and magnetic compass in the establishment of new accessories. I used 20° East magnetic declination.

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 10-92

Rec'd By RF

No. 92-119-R

WB 1004

★GPO: