


Index  
File No. WB 1004  
T 2N R. 37E  
Merid. WILLAMETTE

**CORNER RECORD (SEARCH)**

(Ref. FSM 7151.4)

R.D. WALLA WALLA County UMATILLA Tract or Survey No. \_\_\_\_\_ Cor. No. \_\_\_\_\_  
N.F. UMATILLA State OREGON

**CORNER DIAGRAM**



**DESCRIBE CORNER MONUMENT FOUND**

Corner not previously established.

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

No accessories previously established.

**PHOTO IDENTIFICATION DATA**

Photo No. \_\_\_\_\_  
Filed At. \_\_\_\_\_  
Object Ident. \_\_\_\_\_  
Ident. By \_\_\_\_\_  
*Signature*

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

Corner falls on open West slope approximately 900 feet Southwesterly of the end of the 3150-211 road.

**PLANE COORDINATE POSITION DATA**

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_

*Signature of Surveyor*  
*Agency*

Title SURVEYOR Division \_\_\_\_\_ Headquarters \_\_\_\_\_ Date 9-6-91 FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2"x30" aluminum pipe with aluminum cap marked as shown:  
Pipe is set 28 inches in the ground.

Raised a small mound of stone around the monument.

ELEV 4600  
WB 1004  
1991  
OPLS 644

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New BOs:

A 5/8"x30" iron pin with plastic cap marked BGA SURVEY MARKER bears S78°W, 8.75 feet  
A 5/8"x30" iron pin with plastic cap marked BGA SURVEY MARKER bears N18°W, 6.98 feet

Set a steel fencepost approximately 5 feet Southerly with  
Land Survey Monument and Wilderness Boundary signs attached.

Work Done By. D.I. Griffith Title Surveyor Date 7-25-91 State Registration No. OPLS 644  
or Agency

Certified Cor. Record Prepared? Yes  No Filed At: Umatilla Co. Surveyor Off. Date 10-91

REMARKS

Witness: Jim Bennett