

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:
Corner not previously established.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Corner not previously established.

Description of monument and accessories I established to perpetuate the

original location of this corner: At a point on the Wilderness Boundary line at an Elevation of 4600 feet, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 30 inches in the ground, from which:

New Bearing Trees;


- A 9 inch diameter Ponderosa Pine bears N21°E, 50.80 feet marked WB 980 BT
- A 14 inch diameter Ponderosa Pine bears S84°W, 61.31 feet marked WB 980 BT

Attached Bearing Tree and Land Survey Monument signs to the bearing trees.

Set a steel fencepost approximately 5 feet Easterly with Land Survey Monument and Wilderness Boundary signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on July 8, 1991.

Witnesses: Jeff Petersen, Jim Bennett and John Osterman



**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Duane I. Griffith

OREGON
JULY 10, 1984
DUANE I. GRIFFITH
644

I used a steel tape and magnetic compass in the establishment of new accessories. I used 20° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 10-9-92

Rec'd By KK

No. 92-119-R

☆GPO:

WB 980