


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 17
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 4, 1878, under GLO contract No. 293, as follows:

Set a stone, 17" x 12" x 5", for the corner to sections 2, 3, 10 and 11. Dug pits and drove a pine stake as per instructions.



Original corner evidence recovered:

Found the original corner stone solidly set and surrounded by a mound of small stones. The corner stone is 21" x 12" x 6", and is plainly marked with one notch on the north edge and 2 notches on the east edge. The pits and post of record are gone.

Monument and accessories established to perpetuate the original position of this corner.

In place of the original corner stone, I set a 1" x 30" galvanized iron pipe 12" into the ground to bedrock. A 2 1/2" brass cap attached to the iron pipe is marked as shown in the diagram above. I place the corner stone horizontally along the south side of the pipe and build a mound of stones around the corner stone and pipe, from which:

- A basalt rock outcrop, 5 feet high and 40 feet long, is marked "+ 2" on a protected ledge 3 feet above the ground. The "+" bears N42°E, 97.2 feet.
- A basalt rock outcrop, 4 feet high and 30 feet long, is marked "+11" on a protected ledge one foot above the ground. The "+" bears S63° 30'E, 143.3 feet.
- A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S25°W, 62.9 feet.
- A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N48° 30'W, 117.6 feet.
- A 5 foot steel fence post with a "Witness Post" sign attached bears West, 1.2 feet.

I hereby certify the above corner point was perpetuated as hereon described on June 20, 2000. Magnetic declination set in compass: 18°E.

Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
 Umatilla County Surveyor
 Date 6-2000
 Book XX
00-136-R