


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 3
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 11, 1878, under GLO contract No. 293, as follows:

Set a stone, 18" x 10" x 7", for the 1/4 section corner to sections 6 and 7.



Original corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is 19" x 8" x 6" and is plainly marked "1/4" on the north face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 18" flared, galvanized iron pipe 16" into the ground to bedrock. I bury the corner stone along the north side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N55° E, 100.6 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S67° E, 132.4 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S26° 30' W, 112.7 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N34° W, 69.7 feet.

I hereby certify the above corner point was perpetuated as hereon described on January 28, 2005. Magnetic declination set in compass: 16° E.
NAD '83 UTM Zone 11 position: 5031244N, 332953E (plus or minus two meters).



Dennis L. Gaylord

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
 Umatilla County Surveyor.
 Date 2-05
 Rec'd by KK
 No. 05-26-R