

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P - 17
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 4, 1878, under GLO contract No. 293, as follows:

Set a stone, 14" x 8" x 6", on east hillside for 1/4 section corner.

T2S R30E
1/4
S22|S23
PLS 1636
2002

Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 17" x 8" x 6" and is plainly marked "1/4" on one face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 18" flared, galvanized iron pipe 14" into the ground to bedrock. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the south side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 18" iron rod set 15" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N51° 30' E, 132.6 feet.

A 5/8" x 18" iron rod set 18" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S28° E, 90.7 feet.

A 5/8" x 18" iron rod set 18" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S49° W, 109.3 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N47° W, 119.9 feet.

I nail a "Witness Post" sign to a wooden fence post 1.0 foot north of the corner.

I hereby certify the above corner point was perpetuated as hereon described on March 20, 2002. Magnetic declination set in compass: 18° E.


Dennis L. Gaylord

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 10-02
Rec'd By [Signature]
No. 02-150-R