

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-9  
DIAGRAM

**History of original corner establishment:**

The original corner was established by George S Pershin on September 7, 1878, under GLO contract No. 293, as follows:

Set stone, 18" x 8" x 7", for 1/4 section corner.

T2S R30E  
1/4  
S20|S21  
PLS 1636  
2002

**Original corner evidence recovered:**

Found the original corner stone solidly set 4" into the ground in a mound of stones, but tipped to the south. The corner stone is 16" x 7" x 7" and is plainly marked "1/4" on the east face.

**Monument and accessories established to perpetuate the original position of this corner:**

In place of the corner stone, I set a 1" x 18" flared, galvanized iron pipe 6" into the ground to bedrock. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I place the corner stone horizontally along the west side of the pipe and build a mound of stones around the corner stone and the pipe, from which:

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N66° 30' E, 114.2 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S30° E, 90.1 feet.

A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S62° 30' W, 109.1 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N31° 30' W, 57.0 feet.

The two references to the east are east of a draw.

I hereby certify the above corner point was perpetuated as hereon described on February 25, 2002. Magnetic declination set in compass: 16° E.

  
REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
OREGON  
JULY 14, 1978  
DENNIS L. GAYLORD  
1636

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY  
Umatilla County Surveyor  
Date 6-02  
Rec'd By FR  
No. 02-149-R