


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R - 25  
DIAGRAM

History of original corner establishment:

The original corner was established on October 21, 1871, by George S. Pershin and George Williams under their joint GLO contract No. 154, as follows:

Set stone, 20" x 7" x 5", on east hillside for corner to sections 19, 24, 25 and 30. This corner was subsequently changed to the corner for sections 23, 24, 25 and 26 by the subdivision of T2S, R30 1/2E.



Original corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is 19" x 8" x 5" and is plainly marked with four notches on the north edge.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" galvanized iron pipe 27" into the ground. A 2 1/2" brass cap attached to the iron pipe is marked as shown in the diagram above. I bury the original corner stone along the west side of the pipe and build a mound of stones around the pipe, from which:

- A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S23", attached at ground level, bears N56° 30'E, 72.6 feet.
- A 5/8" x 36" iron rod, set 33" into the ground with a 3/4" brass washer, marked "PLS 1636 S26", attached at ground level, bears S52° 30'E, 89.1 feet.
- A 5/8" x 24" iron rod, set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 S25", attached at ground level, bears S52° 30'W, 88.4 feet.
- A 5/8" x 24" iron rod, set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 S24", attached at ground level, bears N48°W, 133.3 feet.
- A 5 foot steel fence post with a "Witness Post" sign attached bears S15°W, 3.5 feet.

I hereby certify the above corner point was perpetuated as hereon described on October 13, 2000. Magnetic declination set in compass: 18°E.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Dennis L. Gaylord*

OREGON  
JULY 14, 1978  
DENNIS L. GAYLORD  
1636

Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on: 10/17/2000

*David H. Klein*

RECEIVED BY

Umatilla County Surveyor

Date 10-00

Rec'd By KR

No. 00-219-2