


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T - 25
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 7, 1871, under GLO contract No. 154, as follows:

Set a stone, 20" x 14" x 5", on north hillside for 1/4 section corner.



Original corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is 17" x 15" x 5" and is plainly marked "1/4" on the west face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 23" into the ground. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

A 5/8" x 18" iron rod set 16" into the ground, with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N20° 30' E, 105.3 feet.

A 5/8" x 18" iron rod set 17" into the ground, with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S68° E, 61.7 feet.

A 5/8" x 24" iron rod set 22" into the ground, with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S46° W, 84.8 feet.

A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N50° 30' W, 90.9 feet.

This corner marks a point on the Morrow - Umatilla County line.

I hereby certify the above corner point was perpetuated as hereon described on February 10, 2005. Magnetic declination set in compass: 17° E.
NAD '83 UTM Zone 11 position: 5025638N, 331956E (plus or minus two meters).



Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY
 Umatilla County Surveyor
 Date 2-05
 Rec'd by KK
 No. 05-32-R

T-1