

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T - 9
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 7, 1878, under GLO contract No. 293, as follows:

Set a stone, 17" x 8" x 5", for 1/4 section corner.

T2S R30E
1/4
S29|S28
PLS 1636
2002

Original corner evidence recovered:

Found the original corner stone firmly set in a mound of stones. The corner stone is 16" x 7" x 6" and is plainly marked "1/4" on the east face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 18" flared, galvanized iron pipe 15" into the ground to bedrock. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N52° E, 101.4 feet.

A 5/8" x 24" iron rod set 21" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S23° E, 116.9 feet.

A 5/8" x 24" iron rod set 21" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S74° 30' W, 162.5 feet.

A 5/8" x 24" iron rod set 21" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N56° 30' W, 104.2 feet.

I hereby certify this corner point was perpetuated as hereon described on February 6, 2002. Magnetic declination set in compass: 16° E.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**
Dennis L. Gaylord
**OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636**

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on: _____

RECEIVED BY
Umatilla County Surveyor
Date 2-02
Surveyor KK
No. 02-34-R